

NATL INST. OF STAND & TECH



A11107 210826
















19  
24-60412

U. S. DEPARTMENT OF COMMERCE

BUILDING  
MATERIALS  
AND  
STRUCTURES  
REPORT BMS37

Structural Properties of  
"Palisade Homes" Constructions  
for Walls, Partitions, and Floors  
Sponsored by Palisade Homes

by

HERBERT L. WHITTEMORE  
*and* AMBROSE H. STANG

*with the collaboration of*

THOMAS R. C. WILSON,  
Forest Products Laboratory

NATIONAL  
BUREAU OF STANDARDS

JUL 16 1943

54757

The program of research on building materials and structures, carried on by the National Bureau of Standards, was undertaken with the assistance of the Central Housing Committee, an informal organization of Government agencies concerned with housing construction and finance, which is cooperating in the investigations through a subcommittee of principal technical assistants.

CENTRAL HOUSING COMMITTEE  
SUBCOMMITTEE ON TECHNICAL RESEARCH

WALTER JUNGE, *Chairman.*

Federal Housing Administration.

A. C. SHIRE, *Vice Chairman.*

United States Housing Authority.

STERLING R. MARCH, *Secretary.*

ALBERT G. BEAR,  
Veterans' Administration.

GEORGE E. KNOX,  
Yards and Docks (Navy).

PIERRE BLOUKE,  
Federal Home Loan Bank Board (Federal  
Loan Agency).

VINCENT B. PHELAN,  
National Bureau of Standards (Commerce).

CARROLL W. CHAMBERLAIN,  
Public Buildings Administration (Federal  
Works Agency).

EDWARD A. POYNTON,  
Office of Indian Affairs (Interior).

JOSEPH M. DALLAVALLE,  
Public Health Service (Federal Security  
Agency).

GEORGE W. TRAYER,  
Forest Service (Agriculture).

JOHN DONOVAN,  
Farm Security Administration (Agriculture).

ELSMERE J. WALTERS,  
Construction Division (War).

CHAIRMEN OF SECTIONS

*Specifications*

CARROLL W. CHAMBERLAIN

*Materials*

ELSMERE J. WALTERS

*Maintenance*

JOHN H. SCHAEFER

*Mechanical Equipment*

ROBERT K. THULMAN

*Methods and Practices*

NATIONAL BUREAU OF STANDARDS

STAFF COMMITTEE ON ADMINISTRATION AND COORDINATION

HUGH L. DRYDEN, *Chairman.*

Mechanics and Sound.

PHAON H. BATES,  
Clay and Silicate Products.

GUSTAV E. F. LUNDELL,  
Chemistry.

HOBART C. DICKINSON,  
Heat and Power.

ADDAMS S. McALLISTER,  
Codes and Specifications.

WARREN E. EMLEY,  
Organic and Fibrous Materials.

HENRY S. RAWDON,  
Metallurgy.

The Forest Products Laboratory of the United States Department of Agriculture is cooperating with both committees on investigations of wood constructions.

[For list of BMS publications and how to purchase, see cover page III.]

UNITED STATES DEPARTMENT OF COMMERCE · Harry L. Hopkins, Secretary

NATIONAL BUREAU OF STANDARDS · Lyman J. Briggs, Director

# BUILDING MATERIALS

## *and* STRUCTURES

REPORT BMS37

Structural Properties of  
"Palisade Homes" Constructions for Walls, Partitions, and Floors  
Sponsored by Palisade Homes

*by* HERBERT L. WHITTEMORE *and* AMBROSE H. STANG

*with the collaboration of*

THOMAS R. C. WILSON,  
Forest Products Laboratory,  
Forest Service, United States Department of Agriculture



ISSUED FEBRUARY 13, 1940

The National Bureau of Standards is a fact-finding organization;  
it does not "approve" any particular material or method of construction.  
The technical findings in this series of reports are to  
be construed accordingly.



UNITED STATES GOVERNMENT PRINTING OFFICE · WASHINGTON · 1940

FOR SALE BY THE SUPERINTENDENT OF DOCUMENTS, WASHINGTON, D. C. · PRICE 10 CENTS

## Foreword


This report is one of a series issued by the National Bureau of Standards on the structural properties of constructions intended for low-cost houses and apartments. These constructions were sponsored by industrial organizations within the building industry advocating and promoting their use. The sponsor built and submitted the specimens described in this report for participation in the program outlined in report BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions. The sponsor, therefore, is responsible for the design of the constructions and for the description of the materials and of the method of fabrication. The Bureau is responsible for the method of testing and the test results.

This report covers only the load-deformation relations and strength of the walls, partitions, and floors of a house when subjected to compressive, transverse, concentrated, impact, and racking loads by standardized methods simulating the loads to which these elements would be subjected in actual service. Later it may be feasible to determine the heat transmission at ordinary temperatures and the fire resistance of these same constructions and perhaps other properties.

The Forest Products Laboratory, Forest Service, United States Department of Agriculture, collaborated in the tests of those constructions which had wood structural members.

The National Bureau of Standards does not "approve" a construction, nor does it express an opinion as to the merits of a construction for the reasons given in reports BMS1 and BMS2. The technical facts presented in this series provide the basic data from which architects and engineers can determine whether a construction meets desired performance requirements.

LYMAN J. BRIGGS, *Director.*



# Structural Properties of "Palisade Homes" Constructions for Walls, Partitions, and Floors Sponsored by Palisade Homes

by HERBERT L. WHITTEMORE and AMBROSE H. STANG

*with the collaboration of*

Thomas R. C. Wilson, Forest Products Laboratory, Forest Service, United States  
Department of Agriculture

## CONTENTS

	Page		Page
Foreword-----	II	V. Wall <i>CB</i> —Continued.	
I. Introduction-----	2	2. Compressive load-----	8
II. Sponsor and product-----	2	3. Transverse load-----	9
III. Specimens and tests-----	2	4. Concentrated load-----	9
IV. Materials-----	3	5. Impact load-----	10
1. Sponsor's statement-----	3	6. Racking load-----	12
2. Wood-----	3	VI. Partition <i>CC</i> -----	14
(a) Structural members-----	3	1. Sponsor's statement-----	14
(b) Plywood wallboard-----	3	(a) Description-----	14
(c) Flooring-----	3	(b) Comments-----	15
(d) Battens-----	3	2. Concentrated load-----	15
(e) Filler strips-----	4	3. Impact load-----	16
3. Fastenings-----	5	VII. Partition <i>CD</i> -----	16
(a) Nails-----	5	1. Sponsor's statement-----	16
(b) Box strapping-----	6	(a) Description-----	16
(c) Perforated hanger iron-----	6	(b) Comments-----	18
(d) Blind fasteners-----	6	2. Concentrated load-----	18
(e) Corrugated fasteners-----	6	3. Impact load-----	19
(f) Splines-----	6	VIII. Floor <i>CE</i> -----	19
4. Paint-----	6	1. Sponsor's statement-----	19
5. Shellac varnish-----	6	(a) Description-----	19
V. Wall <i>CB</i> -----	6	(b) Comments-----	20
1. Sponsor's statement-----	6	2. Transverse load-----	21
(a) Description-----	6	3. Concentrated load-----	21
(1) Four-foot wall specimens-----	6	4. Impact load-----	23
(2) Eight-foot wall specimens-----	7	IX. Additional comments by sponsor-----	23
(b) Comments-----	8	X. Selected references-----	23

## ABSTRACT

For the program on the determination of the structural properties of low-cost house constructions, Palisade Homes submitted 30 specimens representing their "Palisade Homes" patented construction for walls, partitions, and floors.

The wall specimens were subjected to compressive, transverse, concentrated, impact, and racking loads; the partition specimens to impact and concentrated

loads; and the floor specimens to transverse, concentrated, and impact loads. The transverse, concentrated, and impact loads were applied to both faces of wall specimens. For each of these loads three like specimens were tested. The deformation under load and the set after the load was removed were measured for uniform increments of load, except for concentrated loads, for which the set only was determined. The results are presented in graphs and in tables.

## I. INTRODUCTION

To provide technical facts on the performance of constructions which might be used in low-cost houses, to discover promising new constructions, and ultimately to determine the properties necessary for acceptable performance in actual service, the National Bureau of Standards has invited the cooperation of the building industry in a program of research on building materials and structures suitable for low-cost houses and apartments. The objectives of this program are described in report BMS1, Research on Building Materials and Structures for Use in Low-Cost Housing, and that part of the program relating to structural properties in report BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions.

Masonry constructions and wood constructions of types which have been extensively used in this country for houses were included in the program because their behavior under widely different service conditions is known to builders and the public. The reports on these constructions are BMS5, Structural Properties of Six Masonry Wall Constructions, and BMS25, Structural Properties of Conventional Wood-Frame Constructions for Walls, Partitions, Floors, and Roofs. The masonry specimens were built by the Masonry Construction Section of this Bureau, and the wood-frame specimens were built and tested by the Forest Products Laboratory at Madison, Wis.

The present report describes the structural properties of constructions sponsored by one of the manufacturers in the building industry. The specimens were subjected to compressive, transverse, concentrated, impact, and racking loads, simulating loads to which the elements of a house are subjected. In actual service, compressive loads on a wall are produced by the weight of the roof, second floor and second-story walls if any, furniture and occupants, and snow and wind loads on the roof. Transverse loads on a wall are produced by the wind, concentrated loads by accidental contact with heavy objects, and racking loads by the action of the wind on adjoining walls. For nonload-bearing partitions, impact loads may be applied accidentally by furniture or by a person falling

against a partition, and concentrated loads by a ladder or other object leaning against a partition. Transverse loads are applied to floors by furniture and by the occupants; concentrated loads by furniture, for example, the legs of a piano; and impact loads by objects falling on the floor or by persons jumping on the floor.

The deformation and set under each increment of load were measured because, considered as a structure, the suitability of a construction depends not only on its resistance to deformation when loads are applied but also on whether it returns to its original size and shape when the load is removed.

## II. SPONSOR AND PRODUCT

The specimens were submitted by Palisade Homes of New York, N. Y., and represented constructions patented in the United States and marketed under the trade name "Palisade Homes." These constructions consisted of wood planks with matched edges fitted together to form walls, partitions, and floors. A partition of wood-frame construction also was submitted.

## III. SPECIMENS AND TESTS

The specimens, which represented three elements of a house, were assigned the following symbols: Wall, *CB*; plank partition, *CC*; frame partition, *CD*; and floor, *CE*. The specimens were assigned the designations given in table 1.

TABLE 1.—*Specimen designations*

Element	Construction symbol	Specimen designation	Load	Load applied
Wall	<i>CB</i>	<i>C1, C2, C3</i>	Compressive	Upper end.
		<i>T1, T2, T3</i>	Transverse	Inside face.
		<i>T4, T5, T6</i>	do	Outside face.
		<i>P1, P2, P3</i>	Concentrated	Inside face.
		<i>P4, P5, P6</i>	do	Outside face.
		<i>I1, I2, I3</i>	Impact	Inside face.
Partition (plank)	<i>CC</i>	<i>I4, I5, I6</i>	do	Outside face.
		<i>R1, R2, R3</i>	Racking	Near upper end.
Partition (frame)	<i>CD</i>	<i>P1, P2, P3</i>	Concentrated	Either face.
		<i>I1, I2, I3</i>	Impact	Do.
Floor	<i>CE</i>	<i>P1, P2, P3</i>	Concentrated	Do.
		<i>I1, I2, I3</i>	Impact	Do.

<sup>a</sup> The concentrated and impact loads were applied to the same specimens. The concentrated load was applied first.

The specimens were tested in accordance with BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions, which also gives the requirements for the specimens and describes the presentation of the results of the tests, particularly the load-deformation graphs. Thomas R. C. Wilson, of the Forest Products Laboratory, Madison, Wis., cooperated with the Bureau staff in this work by giving advice and making suggestions on the technique of testing wood structures.

For the compressive test the thickness of the wall was taken as the thickness of the structural portion, that is, the distance from the inside surface of the inward-projecting planks to the outside surface of the outward-projecting planks. The compressive load was applied one-third this thickness from the inside surface of the planks. The shortenings and sets were measured by means of compressometers attached to the steel loading plates through which the load was applied, not to the specimen as described in BMS2. For wood constructions under compressive load there is considerable local shortening caused by crushing of the floor plate and top plate at the ends of the studs. Therefore, the shortening of the entire specimen is not proportional to the value obtained from compressometers attached near each end of the specimen.

The deformations under racking load were measured with a right-angle deformeter consisting of a steel channel and a steel angle braced to form a rigid connection. In use the channel of the deformeter rested along the top of the specimen with the steel angle extending downward in the plane of the specimen. Two pins passed snugly through holes in the channel into the top of the specimen. A dial micrometer was attached to the lower end of the steel angle, with its spindle against the edge of the specimen at the stop. The gage length (distance from the top of the specimen to the micrometer spindle) was 6 ft 10 in. The micrometers were graduated to 0.001 in. and readings were recorded to the nearest division. This deformeter was used instead of the taut-wire mirror-scale device described in BMS2.

Before applying the loads, the speed of the movable head of the testing machine was

measured under no load. For compressive loading the speed was 0.072 in./min. For the transverse loading of walls the speed was 0.4 in./min and of floors 0.25 in./min. These values were recommended by the Forest Products Laboratory.

The tests were begun November 9, 1938, and completed November 28, 1938. The sponsor's representative witnessed the tests.

## IV. MATERIALS

### 1. SPONSOR'S STATEMENT

The information for this statement was obtained from the sponsor and from inspection of the specimens.

The Forest Products Laboratory assisted the sponsor by identifying the species of the wood.

### 2. WOOD

#### (a) Structural Members

Structural members were eastern spruce, merchantable grade, dressed.

One sample of the framing parts (planks, studs, floor plates, top plates, joists, and end members) was taken from each specimen. The samples were identified as spruce (*Picea sp.*)—other than Sitka spruce—with the exception that four of the samples were true fir (*Abies sp.*, probably balsam fir, *Abies balsamea*).

#### (b) Plywood Wallboard

Douglas fir, three-ply, bonded with water-resistant glue, wallboard grade (sound 1 side), sanded,  $\frac{1}{4}$  in. thick.

#### (c) Flooring

Reported by the sponsor as shortleaf pine and identified as one of several species marketed as southern yellow pine, grade No. 2, 25/32 in. thick by  $3\frac{3}{16}$  in. face width (nominal 1 by 4 in), tongued and grooved, but not end-matched.

#### (d) Battens

Ponderosa pine, grade B or better, S4S (surfaced four sides).

(e) *Filler Strips*

Softwood; fir, spruce, and pine, No. 2 common, S4S.

After each specimen was tested one face was removed to expose the structural members and photographs were taken to show the knots and failures. The character of the framing is indicated by figures 1 to 4.



FIGURE 1.—*Wall CB*.

Typical specimen, except that many of the specimens did not show "skip dressing" (dark areas).

The moisture content of the structural members, the wallboard, and the flooring is given in table 2.

TABLE 2.—*Moisture content of the wood*

[Determined on the day the wall, partition, or floor specimen was tested]

Wood	Construction symbol	Moisture content <sup>a</sup>		
		Minimum	Maximum	Average
Structural members, eastern spruce	<i>CB</i>	Percent	Percent	Percent
	<i>CC</i>	10	18	14
	<i>CD</i>	14	22	17
	<i>CE</i>	9	14	12
Average		9	22	13
Wallboard, Douglas-fir plywood	<i>CB</i>	8	16	10
	<i>CC</i>	9	10	10
	<i>CD</i>	11	12	11
Average				10
Flooring, shortleaf pine	<i>CE</i>	8	12	10

<sup>a</sup> Based on the weight when dry.



FIGURE 2.—*Plank partition CC*.

Typical specimen.




FIGURE 3.—*Frame partition CD.*  
Typical specimen.

An electric moisture meter was used when determining the moisture content of the structural members. The instructions with the moisture meter gave correction values for several species of wood. To determine the correction factor for spruce, 30 samples from the planks, joists, and studs were dried in an oven at 212° F until the weight was constant. The moisture content was the difference between the initial weight and the weight when dry, divided by the weight when dry. The average value for these samples was 2.4 greater than the average for the meter readings; therefore the moisture content of the spruce was obtained by adding 2.4 to the average of the meter readings and rounding the result to the nearest whole number.

The moisture content of the wallboard was determined by drying one sample from each specimen in an oven at 212° F until the weight was constant. The moisture content of the flooring was determined, using the moisture meter, and was the uncorrected reading of the meter.

### 3. FASTENINGS

#### (a) Nails

All the nails were made from steel wire except the cut flooring nails. The descriptions are given in table 3.



FIGURE 4.—*Floor CE.*  
Typical specimen.

TABLE 3.—*Description of nails*

Type	Size	Length	Steel Wire Gage	Diam- eter	Finish
		<i>in.</i>	<i>No.</i>	<i>in.</i>	
Box	Penny	2	15 $\frac{1}{2}$	.0672	Bright.
Do.		4	14	.0800	Do.
Box, coolers		6	17 $\frac{1}{2}$	.0915	Cement coated.
Car, heavy		4	1 $\frac{1}{2}$	.1350	
Common		6	2	.11 $\frac{1}{2}$	.1130
Do.		8	2 $\frac{1}{2}$	.10 $\frac{1}{4}$	.1314
Do.		10	3	.09	.1483
Finishing		20	4	.10	.1350
Flooring, cut		6	2		Blued or bright.
Lath		3	1 $\frac{1}{8}$	.0720	
Plasterboard			1 $\frac{1}{2}$	.0915	
Roofing, barbed			3 $\frac{1}{4}$	.1483	Bright.
Do.			7 $\frac{1}{8}$	.1055	Do.
Do.			1	.1055	Do.
Shingle		6	2	.12	Do.

(b) *Box Strapping*

Sheet steel, either  $\frac{3}{4}$  in. or  $\frac{5}{8}$  in. wide, No. 28 U. S. Std. Gage (0.0156 in. thick).

(c) *Perforated Hanger Iron*

Sheet steel, 1 in. wide, No. 20 U. S. Std. Gage (0.0375 in. thick) having two rows of  $\frac{3}{16}$ -in. holes,  $\frac{1}{8}$  in. apart, spaced  $1\frac{1}{16}$  in. on centers, and also a row of slots at midwidth,  $\frac{3}{16}$  by  $\frac{3}{4}$  in., spaced  $1\frac{1}{16}$  in. on centers.

(d) *Blind Fasteners*

Sheet steel,  $1\frac{1}{8}$  by  $1\frac{3}{16}$  in., No. 24 U. S. Std. Gage (0.0245 in. thick), having five stamped prongs projecting  $\frac{1}{4}$  in. and a slot,  $\frac{3}{32}$  in. wide, extending  $\frac{7}{16}$  in. inward from one edge. Upson Board Co.

(e) *Corrugated Fasteners*

Sheet steel, 1 in. wide,  $\frac{5}{8}$  in. long, No. 24 U. S. Std. Gage (0.0245 in. thick), five corrugations.

(f) *Splines*

Sheet steel, 1 by 4 in., No. 16 U. S. Std. Gage (0.0625 in. thick).

## 4. PAINT

Lead and oil, slate gray. Devoe & Raynolds Co.'s No. 562.

## 5. SHELLAC VARNISH

White shellac, 5 lb of shellac to 1 gal of alcohol. "Aeme" brand.

## V. WALL CB


## 1. SPONSOR'S STATEMENT

(a) *Description*

Wall *CB* was a wood-plank construction having plywood wallboard on the inside face.

The price in Washington, D. C., as of July 1937, was \$0.365/ft<sup>2</sup>.

(1) *Four-foot wall specimens.*—The 4-ft wall specimens were 8 ft 2 in. high, 4 ft 0 in. wide, and  $2\frac{3}{4}$  in. thick. Each specimen consisted of six specially edge-matched planks, *A*, as shown in figure 5, so assembled that alternate planks projected  $\frac{1}{4}$  in. from the adjacent planks. The planks were fastened to a grooved floor plate, *B*, and a grooved top plate, *C*, by nails.

FIGURE 5.—*Four-foot wall specimen CB.*

*A*, planks; *B*, floor plate; *C*, top plate; *D*, filler strip; *E*, plywood wallboard.

The outer surface of the planks formed the outside face of the wall. The inside face of the wall was plywood wallboard, *E*, shown in

figure 6, nailed to the planks and to vertical filler strips, *D*, and to horizontal filler strips, *F*.




FIGURE 6.—Details of wall specimen *CB*.

*A*, planks; *B*, floor plate; *C*, top plate; *D*, filler strip; *E*, plywood wallboard; *F*, filler strip.

The outside face, floor plate, top plate, and edges of the specimens were covered with one coat of lead-and-oil paint. The inside face was covered with one coat of shellac varnish. Both paint and shellac were applied with a brush.

**Planks.**—The planks, *A*, were eastern spruce,  $1\frac{1}{4}$  by  $8\frac{1}{32}$  in. (nominal 2 by 9 in.), 7 ft  $11\frac{3}{4}$  in. long. The planks matched as shown in figure 6, resulting in a wall surface with every alternate plank projecting  $\frac{3}{4}$  in. outward from adjacent planks. After assembly the planks were held by box strapping on the inside face, as shown in figure 1. The strapping intended for each specimen consisted of two horizontal pieces, one near the bottom, the other near the top; and of four diagonal pieces, two across the lower half and two across the upper half of the

specimen. However, in most specimens one or two diagonals were omitted. The strapping was fastened to each inward-projecting plank by three nails—either 4d box nails or  $\frac{3}{4}$ - or 1-in. roofing nails. The strapping was not taut. The planks were also fastened at each vertical joint by two to six 4d ear nails toenailed from the inside.

**Floor plate and top plate.**—The floor plate, *B*, and the top plate, *C*, were spruce,  $1\frac{1}{4}$  by  $3\frac{3}{8}$  in. (nominal 2 by 4 in.), 4 ft 1 in. long, with a  $2\frac{1}{2}$ - by  $\frac{5}{8}$ -in. groove. The ends were parallel and beveled 1 in. across the width of the plate (thickness of the wall). The plates fitted over the ends of the planks, as shown in figure 6, and were fastened to each plank by one or two 10d common nails or 20d finishing nails driven from the bottom of the floor plate and the top of the top plate. Five to eight 6d common nails or 6d shingle nails were driven through the inner lip of the floor plate and of the top plate into the planks projecting inward.

**Filler strips.**—The edge filler strip, *D*, was  $\frac{3}{8}$  by  $1\frac{1}{2}$  in., 7 ft  $9\frac{1}{4}$  in. long, and was at one edge of the specimen, fastened to the projecting plank by 2d box nails spaced 1 ft. This strip is not used in a house. Horizontal filler strips, *F*,  $\frac{3}{8}$  by  $\frac{5}{8}$  in.,  $7\frac{5}{16}$  in. long, were fastened near the top and bottom of each alternate plank by two 2d box nails.

**Plywood wallboard.**—The wallboard, *E*, was  $\frac{1}{4}$ -in. Douglas-fir plywood, 7 ft  $10\frac{1}{2}$  in. by 4 ft 0 in. It was fastened to the planks and filler strips by 3d lath nails, spaced 6 to 10 in. along the top and bottom edges of the board and about 12 in. along the vertical edges. The grain of the outer plies was vertical. Battens,  $\frac{3}{8}$  by  $1\frac{1}{2}$  in., 7 ft  $10\frac{1}{2}$  in. long, were placed vertically over the plywood wallboard at midwidth and at one edge and were fastened by 6d common nails spaced 13 in., driven through the battens and wallboard into the planks.

(2) **Eight-foot wall specimens.**—The 8-ft wall specimens were 8 ft 2 in. high, 8 ft 0 in. wide, and  $2\frac{3}{4}$  in. thick. The specimens were similar to the 4-ft specimens except for the following details. A strip of perforated hanger iron was fastened along the top and bottom ends of the planks by  $\frac{3}{4}$ -in. roofing nails spaced about  $3\frac{1}{2}$  in. Three pieces of box strapping were fastened to the planks, one horizontally at

midheight and the other two diagonally between the corners of the specimen. In addition, on specimens *R2* and *R3* there was a shorter piece of strapping placed diagonally from midheight at one edge to midwidth at the top of specimen *R2* and to midwidth at the bottom of *R3*. The floor plate and top plate were fastened to each plank by two 10d common nails. The wallboard was two pieces of plywood, 7 ft 10½ in. by 4 ft 0 in., having a vertical joint at midwidth and fastened in the same way as the wallboard of the 4-ft specimens by 3d lath nails, spaced 6 to 10 in. along the top and bottom edges and about 12 in. along the vertical edges. The grain of the outer plies was vertical.

(b) *Comments*

Planks are available in soft woods—fir, pine, spruce, and hemlock—and in sizes ranging from 1¼ to 3 in. in thickness, and from 3½ to 9½ in. in width.

In a house of this construction the walls are supported by a masonry foundation wall. A 3- by 8-in. dressed-wood sill of a dense, durable species is bolted flatwise to the foundation with the outer edge projecting about ½ in. In the upper surface of the sill there is a saw kerf, ½ in. wide by ½ in. deep. A continuous steel spline ½ by 1 in. is inserted in this slot and serves to align the wall planks as they are placed in position. There are similar saw kerfs in both ends of the wall planks along the center line of the wall.

Either the outer joist of the floor or a ranger, 2 by 4 in., is spiked edgewise to the sill at a distance of one-half the thickness of the wall inside the saw kerf. The sill and ranger are mopped with a waterproof asphalt-bitumen compound. Five or six planks are assembled and drawn together by boat clamps, set in place, and spiked to either the floor joist or the ranger. The sill projects about 1 in. beyond the outward-projecting planks.

Before the sill is laid, the upper edge is chamfered at 45° to drip the faces of the outward-projecting planks. After the planks are in place, the sill between the outer planks is beveled at 30° to drip the faces of the recessed planks.

The top plate may be softwood, 2 by 4 in., but

preferably hardwood, 1½ by 5 in., for better alignment and more secure nailing. The plate is connected to the wall planks by a steel spline which fits into saw kerfs in the top of the planks and in the lower surface of the plate, and is fastened by nails passing through the plate into the planks.

Door and window frames are planks matched to fit the wall planks. Diagonal bracing in the walls may be provided by special shear fasteners in the vertical joints between planks, by heavy box strapping fastened diagonally to the inside surface of the planks, or by diagonal furring for lath and plaster or other finishing.

Instead of assembling the planks on the building site, prefabricated units may be assembled in a shop, each consisting of eight or more prime-coated planks. Some of the advantages of prefabricated units are more rapid erection and lower cost.

The wall planks may serve as outside face as well as structural members, and two or three coats of paint complete the outside finish; although, if desired, conventional finishes, such as drop siding, lap siding, or shingles, may be readily applied. Lath and plaster or wallboard may be applied for inside finish. The spaces formed by alternate planks serve as chases for conduit and piping and, if closed by the interior and exterior finishes, decrease the heat transmission through the wall.

For a two-story house, about one-fourth of the planks are full height. Shorter planks are placed above or below openings and may be spliced if they extend the full height.

## 2. COMPRESSIVE LOAD

Wall specimen *CB-C1* under compressive load is shown in figure 7. The results for wall specimens *CB-C1*, *C2*, and *C3* are shown in table 4 and in figures 8 and 9.

The lateral deflections shown in figure 9 were plotted to the right of the vertical axis for deflections of the specimen toward the outside face (positive deflection) and to the left for deflections toward the inside face (negative deflection).

Although the load was eccentric toward the inside face, specimens *C1* and *C2* deflected initially toward the inside face, whereas speci-

men *C3* deflected toward the outside face. As the load was increased, the deflection of specimen *C1* did not change appreciably and at the maximum load it was zero. The deflection of specimen *C2* decreased to zero and then increased slightly toward the outside face up to the maximum load. Specimen *C3* deflected toward the outside face throughout the test. The lateral deflection toward the inside face was probably due to the stiffness of the inside face offsetting the effect of the eccentric loading. The change in direction of the deflections of

specimens *C1* and *C2* indicated buckling of the inside face.

Each of the specimens failed by crushing of the inside edge of the top plate locally at the ends of the planks, causing the top plate to rotate and allowing the specimens to push out under load without breaking the planks. In addition, on specimen *C1* the plywood wallboard separated from the planks near the top plate by pulling the nails from the planks; in specimen *C2* the top plate split; and in specimen *C3* the top plate pulled the nails from the planks.

TABLE 4.—*Structural properties, wall CB*

[Weight, 5.24 lb/ft<sup>2</sup>]

Load	Load applied	Specimen designation	Failure of loaded face, height of drop	Failure of opposite face, height of drop	Maximum height of drop	Maximum load
Compressive	{Upper end, one-third the thickness (0.83 in.) from the inside surface of the planks (see section III).}	<i>C1</i>	ft	ft	ft	<sup>a</sup> Kips/ft
		<i>C2</i>				10.00
		<i>C3</i>				10.00
		Average				9.70
Transverse	Inside face; span, 7 ft 6 in.	<i>T1</i>				lb/ft <sup>2</sup>
		<i>T2</i>				500
		<i>T3</i>				546
		Average				479
Do	Outside face; span, 7 ft 6 in.	<i>T4</i>				546
		<i>T5</i>				582
		<i>T6</i>				538
		Average				555
Concentrated	Inside face	<i>P1</i>				lb
		<i>P2</i>				700
		<i>P3</i>				650
		Average				510
Do	Outside face	<i>P4</i>				b 1,000
		<i>P5</i>				b 1,000
		<i>P6</i>				b 1,000
		Average				b 1,000
Impact	Inside face; span, 7 ft 6 in.	<i>I1</i>	(e)	(e)	b 10.0	
		<i>I2</i>	(e)	(e)	b 10.0	
		<i>I3</i>	(e)	(e)	b 10.0	
		Average	(e)	(e)	b 10.0	
Do	Outside face; span, 7 ft 6 in.	<i>I4</i>	7.0	(e)	b 10.0	
		<i>I5</i>	(e)	(e)	b 10.0	
		<i>I6</i>	7.0	(e)	b 10.0	
		Average	(e)	(e)	b 10.0	
Racking	Near upper end	<i>R1</i>				<sup>a</sup> Kips/ft
		<i>R2</i>				0.454
		<i>R3</i>				.404
		Average				.360

<sup>a</sup> A kip is 1,000 lb.

<sup>b</sup> Test discontinued. Specimen did not fail.

<sup>c</sup> Face did not fail.

### 3. TRANSVERSE LOAD

The results under transverse load are shown in table 4 and in figure 10 for wall specimens *CB-T1*, *T2*, and *T3*, loaded on the inside face, and in figure 11 for wall specimens *CB-T4*, *T5*, and *T6*, loaded on the outside face.

In specimen *T1* at a load of 400 lb/ft<sup>2</sup> two planks ruptured at or between the loading rollers, and at the maximum load the specimen failed by rupture of two more planks between the loading rollers. Specimen *T2* failed at maximum load by rupture of all the planks at a loading roller. In specimen *T3* at a load of 450 lb/ft<sup>2</sup> one plank ruptured between the loading rollers and at the maximum load the specimen failed by rupture near midspan of three more planks. The plywood wallboard of the specimens was undamaged, but on specimen *T1* it had separated from the planks.

At the maximum loads specimens *T4*, *T5*, and *T6* failed by rupture of all or all but one of the planks at or between the loading rollers. The plywood wallboard was undamaged but separated from the planks at the ruptures and at the ends of the specimens by pulling the nails from the planks.

### 4. CONCENTRATED LOAD

The results of the concentrated-load tests are shown in table 4 and in figure 12 for wall specimens *CB-P1*, *P2*, and *P3*, loaded on the inside face, and in figure 13 for wall specimens *CB-P4*, *P5*, and *P6*, loaded on the outside face.

The concentrated loads were applied to the inside face of specimens *P1*, *P2*, and *P3* on the plywood wallboard over the cavity between the wallboard and a projecting plank, about 2




FIGURE 7.—Wall specimen *CB-C1* under compressive load.

ft from one end. Each of the specimens failed by punching of the disk through the wallboard.

The concentrated loads were applied to the outside face of specimens *P*<sub>4</sub>, *P*<sub>5</sub>, and *P*<sub>6</sub> on a plank, about  $2\frac{1}{2}$  ft from the top end. The indentations after a load of 1,000 lb had been applied were 0.047, 0.111, and 0.055 in. in specimens *P*<sub>4</sub>, *P*<sub>5</sub>, and *P*<sub>6</sub>, respectively, and no other effect was observed.

##### 5. IMPACT LOAD

The results of the impact test are shown in table 4 and in figure 14 for wall specimens

*CB-I1*, *I2*, and *I3*, loaded on the inside face, and in figure 15 for wall specimens *CB-I4*, *I5*, and *I6*, loaded on the outside face.




FIGURE 8.—Compressive load on wall *CB*.

Load-shortening (open circles) and load-set (solid circles) results for specimens *CB-C1*, *C2*, and *C3*. The load was applied one-third the thickness (0.83 in.) from the inside surface of the planks. The loads are in kips per foot of actual width of specimen.

The impact loads were applied to the center of the inside face of specimens *I1*, *I2*, and *I3*, the sandbag striking the center batten and the wallboard. At drops of 3, 5, and 10 ft for specimens *I1*, *I2*, and *I3*, respectively, there was noticeable opening of the joint between the center planks where the sandbag struck. In addition, in specimen *I2* at a drop of 7.5 ft the floor plate split at the edge of the specimen and the filler strip along the edge separated from the plank. The sets after a drop of 10 ft were 0.177, 0.096, and 0.114 in. for specimens *I1*, *I2*, and *I3*, respectively, and no other effect was observed.

The impact loads were applied to the center of the outside face of specimens *I4*, *I5*, and *I6*, the sandbag striking the planks. In specimen *I4* at a drop of 4.5 ft there was noticeable opening of the joint between the two center planks




FIGURE 9.—Compressive load on wall CB.

Load-lateral deflection (open circles) and load-set (solid circles) results for specimens *CB-C1*, *C2*, and *C3*. The load was applied one-third the thickness (0.83 in.) from the inside surface of the planks. The loads are in kips per foot of actual width of specimen. The deflections and sets are for a gage length of 7 ft 10 in., the gage length of the deflectometers.




FIGURE 10.—Transverse load on wall CB, load applied to inside face.

Load-deflection (open circles) and load-set (solid circles) results for specimens *CB-T1*, *T2*, and *T3* on the span 7 ft 6 in.




FIGURE 11.—Transverse load on wall CB, load applied to outside face.

Load-deflection (open circles) and load-set (solid circles) results for specimens *CB-T4*, *T5*, and *T6* on the span 7 ft 6 in.




FIGURE 12.—Concentrated load on wall CB, load applied to inside face.

Load-indentation results for specimens *CB-P1*, *P2*, and *P3*.




FIGURE 13.—Concentrated load on wall CB, load applied to outside face.

Load-indentation results for specimens CB-P4, P5, and P6.




FIGURE 14.—Impact load on wall CB, load applied to inside face.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens CB-11, I2, and I3 on the span 7 ft 6 in.




FIGURE 15.—Impact load on wall CB, load applied to outside face.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens CB-I4, I5, and I6 on the span 7 ft 6 in.

near midspan, and at a drop of 7 ft the planks separated at the matched joint, causing failure of the outside face. At a drop of 9 ft the battens started to separate from the plywood wallboard by pulling the nails from the planks at one edge of the specimen. At the 10-ft drop the floor plate and top plate separated from the planks, and the floor plate split. The set after a drop of 10 ft was 0.132 in. In specimen I5 at a drop of 5.5 ft the top plate split, and at the 6.5-ft drop there was noticeable displacement between the two center planks at midspan. The set after a drop of 10 ft was 0.042 in. In specimen I6 at a drop of 7 ft the joint between the two center planks opened at midspan, causing failure of the outside face. At a drop of 8.5 ft the edge filler strip separated from the plank, and at a drop of 9.5 ft the edge batten also separated. The set after a drop of 10 ft was 0.124 in.

## 6. RACKING LOAD

Wall specimen CB-R2 under racking load is shown in figure 16. The results for wall specimens CB-R1, R2, and R3 are shown in table 4 and in figure 17.

The load was applied to the edge of the plank at one upper corner of the specimen and the stop was in contact with the edge of the plank at the diagonally opposite corner. In

able vertical displacement of the plywood wallboard panels at the joint in the wallboard. Under a load of 0.350 kip/ft there was noticeable vertical displacement at all the joints



FIGURE 16.—Wall specimen *CB-R2* under racking load.

specimen *R1* at a load of 0.312 kip/ft the plywood wallboard separated from the loaded edge of the specimen, pulling the nails from the plank and the filler strip. There was noticeable

vertical displacement of the plywood wallboard panels at the joint in the wallboard. Under a load of 0.350 kip/ft there was noticeable vertical displacement at all the joints

planks, and the top plate had bowed upward at midwidth.

In specimens *R2* and *R3* at loads of 0.240 and 0.200 kip/ft, respectively, there was noticeable vertical displacement at the joint in the




FIGURE 17.—Racking load on wall *CB*.

Load-deformation (open circles) and load-set (solid circles) results for specimens *CB-R1*, *R2*, and *R3*. The loads are in kips per foot of actual width of specimen.

wallboard; and at loads of 0.320 and 0.360 kip/ft respectively, the wallboard separated from the loaded edge of the specimens. At the maximum loads each of the specimens failed by continued slipping of the planks at the joints. The wallboard had pulled the nails from the planks, and the top plate had bowed upward at midwidth. Also the floor plate of specimen *R3* had separated from the planks, leaving the nails in the planks.

## VI. PARTITION *CC*

### 1. SPONSOR'S STATEMENT

#### (a) Description

Partition *CC* was a wood-plank construction having plywood wallboard on both faces. It was similar to wall *CB* except that the planks were  $1\frac{1}{8}$  by  $5\frac{3}{8}$  in., not  $1\frac{1}{4}$  by  $8\frac{1}{32}$  in.; they projected  $\frac{1}{4}$  in., not  $\frac{3}{4}$  in.; and the edges were

tongued and grooved, not edge-matched. Also, both faces were plywood wallboard, not one face.

The price in Washington, D. C., as of July 1937, was \$0.40/ft<sup>2</sup>.

The plank partition specimens shown in figure 18, were 8 ft 2 in. high, 4 ft  $\frac{3}{8}$  in. wide, and  $1\frac{1}{8}$  in. thick. Each specimen consisted of nine tongue-and-grooved planks, *A*, so assembled that alternate planks projected  $\frac{1}{4}$  in. The planks were fastened to a floor plate, *B*, and a top plate, *C*, by splines. The faces consisted of plywood wallboard, *D*. The floor plate, top plate, and edges of the specimens were covered




FIGURE 18.—Partition specimen *CC*.

*A*, planks; *B*, floor plate; *C*, top plate; *D*, plywood wallboard.

with one coat of lead-and-oil paint. The faces were covered with one coat of shellac varnish. Both paint and shellac were applied with a brush.

*Planks*.—The planks, *A*, were spruce,  $1\frac{1}{8}$  by  $5\frac{3}{8}$  in., 7 ft  $10\frac{1}{16}$  in. long. The edges of each plank were tongued and grooved on a line  $\frac{1}{8}$  in. from midthickness, and the planks were assem-

bled as shown in figure 19. After assembly the planks were held by box strapping fastened to both faces. The strapping consisted of two horizontal strips, one near the bottom, the other near the top, and one strip applied diagonally




FIGURE 19.—*Details of partition specimen CC.*

*A*, planks; *B*, floor plate; *C*, top plate; *D*, plywood wallboard; *E*, filler strip.

from a lower to an upper corner, as shown in figure 2. The strapping was fastened to each projecting plank by two nails—either 3d lath nails or  $\frac{3}{8}$ -in. or 1-in. roofing nails. After assembling the planks, the upper and lower ends of the assembled unit were grooved  $\frac{1}{8}$  by  $\frac{1}{2}$  in. at midthickness.

*Floor plate.*—The floor plate, *B*, was spruce,  $1\frac{1}{8}$  by  $11\frac{3}{16}$  in., 4 ft  $1\frac{1}{8}$  in. long, having  $\frac{1}{16}$ - by  $\frac{1}{4}$ -in. recesses at two edges. The ends were parallel and beveled 1 in. The plate was connected to the planks by five steel splines spaced along a  $1\frac{1}{16}$ - by  $\frac{1}{2}$ -in. groove in the plate and fitted into the groove in the planks.

*Top plate.*—The top plate, *C*, was spruce,  $1\frac{1}{8}$  by  $1\frac{1}{4}$  in., 4 ft  $1\frac{1}{8}$  in. long, having  $\frac{1}{2}$ - by  $\frac{1}{4}$ -in. recesses at two edges. The ends were parallel

and beveled 1 in. The plate was connected to the planks by five splines spaced along a  $1\frac{1}{16}$ - by  $\frac{1}{2}$ -in. groove in the plate and fitted into the groove in the planks.

*Plywood wallboard.*—The wallboard, *D*, was  $\frac{1}{4}$ -in. Douglas-fir plywood, 8 ft 0 in. by 4 ft 0 in. The edges of the wallboard fitted into the recesses in the floor plate and top plate, and were fastened by 3d lath nails spaced 5 in., driven through the wall board into the plates. The wallboard was fastened to the planks by blind fasteners, spaced 16 in. along both vertical edges and along the vertical center line of the specimen. On one side of the specimen each fastener was attached by a 3d lath nail directly to the planks, on the other side to the filler strips. The grain of the outer plies was vertical.

*Filler strips.*—The filler strips, *E*, were  $\frac{1}{4}$  by  $1\frac{1}{2}$  in., 7 ft  $10\frac{1}{16}$  in. long. There were three strips on one side of the specimen, fastened to the recessed planks at the edges and at midwidth by 3d lath nails.

#### (b) *Comments*

Partition planks are available in soft woods, such as fir, pine, spruce, and hemlock; and in sizes ranging from  $1\frac{1}{16}$  to  $1\frac{1}{8}$  in. thickness and from  $3\frac{1}{4}$  to  $9\frac{1}{2}$  in. in width. In a house the ends of the planks rest on a wood floor plate fastened to the subfloor and fitted with a steel spline which holds the planks in place. A wood top plate similar to the floor plate and nailed either to the ceiling joists or to the second-story floor joists fastens the planks at the top.

The partition may be used without additional finishes other than paint or varnish. However, other finishes, such as lath and plaster or any kind of wallboard, may readily be applied to the planks.

#### 2. CONCENTRATED LOAD

Partition specimen *CC-P1* under concentrated load is shown in figure 20. The results for partition specimens *CC-P1*, *P2* and *P3* are shown in table 5 and in figure 21.

The concentrated loads were applied to one face of specimens *P1*, *P2*, and *P3* on the wallboard over the cavity between the wallboard

TABLE 5.—*Structural properties, partition CC*  
[Weight, 4.20 lb/ft<sup>2</sup>]

Load	Load applied	Specimen designation	Maximum height of drop	Maximum load
Concentrated	One face	<i>P<sub>1</sub></i>	ft	lb
		<i>P<sub>2</sub></i>		
Impact	One face, span, 7 ft 6 in.	<i>P<sub>3</sub></i>	a 10.0	a 1,000
		<i>I<sub>1</sub></i>		
	Average	<i>I<sub>2</sub></i>	a 10.0	a 1,000
		<i>I<sub>3</sub></i>		
		Average	a 10.0	—

<sup>a</sup> Test discontinued. Specimen did not fail.




FIGURE 20.—*Partition specimen CC-P1 under concentrated load.*

and a plank, about 2 ft from one end. The indentations after a load of 1,000 lb had been applied were 0.062, 0.080, and 0.082 in. for specimens *P<sub>1</sub>*, *P<sub>2</sub>*, and *P<sub>3</sub>*, respectively, and no other effect was observed.

### 3. IMPACT LOAD

The results of the impact tests for partition specimens *CC-I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>* are shown in table 5 and in figure 22.

The impact loads were applied to one face of the specimens, the sandbag striking the plywood wallboard. At drops of 4, 5, and 4 ft for specimens *I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>*, respectively, the wallboard started to separate from the planks. The sets after a drop of 10 ft were 0.180, 0.145,

and 0.000 in. for specimens *I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>*, respectively, and both plywood-wallboard faces were separated from the planks. The zero set of specimen *I<sub>3</sub>* was due to the springing upward of the loose wallboard.

## VII. PARTITION *CD*

### 1. SPONSOR'S STATEMENT

#### (a) Description

Partition *CD* was a wood-frame construction having plywood wallboard on both faces and

was similar to partition *CC* except that the structural members were studs and not planks.

The price in Washington, D. C., as of July 1937, was \$0.285/ft<sup>2</sup>.

The frame partition specimens, shown in figure 23, were 8 ft 2 in. high, 4 ft 0 in. wide, and 2 in. thick. Each specimen consisted of a wood frame to which the faces were fastened. The frame consisted of three full-sized studs, *A*, and two half-sized studs, *B*, fastened to a floor plate, *C*, and a top plate, *D*. The faces consisted of plywood wallboard, *E*. The floor plate, top plate, and edges of the specimen were covered with one coat of lead-and-oil paint. The faces were covered with one coat of shellac varnish. Both paint and shellac were applied with a brush.




FIGURE 21.—Concentrated load on partition CC.

Load-indentation results for specimens CC-PI, P2, and P3.




FIGURE 22.—Impact load on partition CC.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens CC-II, I2, and I3 on the span 7 ft 6 in.

*Studs.*—The full-sized studs, *A*, were spruce,  $1\frac{3}{8}$  by  $1\frac{1}{4}$  in., 7 ft  $11\frac{1}{8}$  in. long, with  $\frac{3}{8}$ - by  $\frac{1}{4}$ -in. recesses in two edges, as shown in figure 24. They were spaced 1 ft 0 in. on centers.

The half-sized studs, *B*, were spruce,  $2\frac{5}{32}$  by  $1\frac{1}{4}$  in., 7 ft  $11\frac{1}{8}$  in. long, with a  $\frac{3}{8}$ - by  $\frac{1}{4}$ -in. recess in one edge and were at the edges of the specimen.

*Floor plate.*—The floor plate, *C*, was spruce,  $1\frac{5}{8}$  by  $2\frac{1}{16}$  in., 4 ft 1 in. long, with two




FIGURE 23.—Partition specimen CD.

*A*, full-sized stud; *B*, half-sized stud; *C*, floor plate; *D*, top plate; *E*, plywood wallboard.

grooves on the upper surface. The ends were parallel and beveled 1 in. The center stud was fastened to the floor plate by one 8d common nail driven through the floor plate into the stud. Each of the two outer full-sized studs was fastened to the floor plate by two pieces of box strapping which passed through two  $\frac{3}{4}$ -in. diam holes in the floor plate, and were fastened to each edge of the stud by two 3d lath nails.

*Top plate.*—The top plate, *D*, was spruce, 1 by  $2\frac{1}{16}$  in., 4 ft 1 in. long, with two grooves on

the lower surface. The ends were parallel and beveled 1 in. The top plate was fastened to the center stud by one 6d common nail driven through the top plate into the stud, and to the two outer full-sized studs by a piece of box




FIGURE 24.—*Details of partition specimen CD.*

*A*, full-sized stud; *B*, half-sized stud; *C*, floor plate; *D*, top plate; *E*, plywood wallboard; *F*, batten.

strapping passing through two  $\frac{3}{4}$ -in. diam holes in the top plate. The box strapping was fastened to each edge of the stud by two 3d lath nails.

*Plywood wallboard.*—The wallboard, *E*, was  $\frac{1}{4}$ -in. Douglas-fir plywood, 8 ft  $\frac{1}{8}$  in. high and either 1 ft  $11\frac{1}{8}$  in. or  $11\frac{1}{8}$  in. wide. The boards fitted into the grooves in the floor plate and top plate and into the recesses in the full-sized studs and half-sized studs. One face consisted of two of the wide pieces of wallboard with a vertical joint on the center stud. The other face consisted of one of the wide pieces and two of the narrow pieces with vertical joints on the outer full-sized studs. The wallboard was fastened to the recesses in the full-

sized studs and to both sides of the half-sized studs by 3d lath nails, spaced about 5 in., and to the other side of the full-sized studs by blind fasteners, spaced about 12 in. Each fastener was attached to the stud by a 3d lath nail driven through the slot in the fastener. The grain of the outer plies of the wallboard was vertical.

*Battens.*—The battens, *F* (astragal molding), were  $\frac{1}{8}$  by  $1\frac{1}{4}$  in., 7 ft  $11\frac{1}{2}$  in. long, with the exposed face cut to an O-gee-and-fillet mold. They were placed at the joints between the plywood wallboard and the full-sized studs, over the recessed edges of the studs, and fastened with 4d box nails, spaced 10 in.

(b) *Comments*

Construction *CD* is a nonload-bearing partition, such as a closet partition. It is designed for ease in assembly, and can be taken apart and reassembled if a change of location is desired. The floor plate and top plate are fastened to the floor and ceiling, respectively, and the plywood wallboard and studs are placed in position alternately.

## 2. CONCENTRATED LOAD

The results of the concentrated-load tests on partition specimens *CD-P1*, *P2*, and *P3* are shown in table 6 and in figure 25.

TABLE 6.—*Structural properties, partition CD*

[Weight, 2.10 lb/ft<sup>2</sup>]

Load	Load applied	Speci- men desig- nation	Fail- ure of loaded face, height of drop	Fail- ure of oppo- site face, height of drop	Maxi- mum height of drop	Maxi- mum load
Concentrated	One face	$\begin{cases} P1 \\ P2 \\ P3 \end{cases}$	ft	ft	ft	lb
			-----	-----	-----	550
			-----	-----	-----	450
			-----	-----	-----	440
	Average		-----	-----	-----	480
Impact	One face; span, 7 ft 6 in	$\begin{cases} I1 \\ I2 \\ I3 \end{cases}$	4.5	4.5	7.5	-----
			4.5	4.0	7.5	-----
			4.5	4.0	7.0	-----
	Average		4.5	4.2	7.3	-----

The concentrated loads were applied to the plywood wallboard midway between full-sized studs and from 2 to  $2\frac{1}{2}$  ft from one end of the specimen. At the maximum load each of the




FIGURE 25.—Concentrated load on partition *CD*.  
Load-indentation results for specimens *CD-PI*, *P2*, and *P3*.

specimens failed by punching of the disk through the wallboard.

### 3. IMPACT LOAD

Partition specimen *CD-I3* during the impact test is shown in figure 26. The results for partition specimens *CD-I1*, *I2*, and *I3* are shown in table 6 and in figure 27.

The impact loads were applied to one face of the specimens, the sandbag striking the center batten and the wallboard. On specimen *I1* at a drop of 3.5 ft the plywood wallboard of the face struck separated from the stud under the center batten. After the 4-ft drop the battens on the opposite face were loose, and at the 4.5-ft drop both faces failed by complete separation of the wallboard from the studs and opening of the joints under the battens. At a drop of 6.5 ft two full-sized studs and one half-sized stud ruptured and the floor plate

and the top plate split. At the maximum drop the remaining studs ruptured and the specimen broke in two along the center stud. On specimens *I2* and *I3* at drops of 4 ft the face not struck failed by opening of the joint under one batten, and at drops of 4.5 ft the face struck failed by opening of the joint under the center batten. In specimen *I2* at a drop of 5 ft the center stud ruptured, at a drop of 5.5 ft one outer full-sized stud ruptured, and at the maximum drop the specimen broke in two and the top plate separated from the studs. In specimen *I3* at a drop of 5.5 ft the center stud ruptured, at a drop of 6 ft the two outer full-sized studs ruptured, and at the maximum drop the specimen broke in two.

## VIII. FLOOR *CE*

### 1. SPONSOR'S STATEMENT

#### (a) Description

Floor *CE* was a wood plank-and-joist construction having wood flooring on the upper face.




FIGURE 26.—Partition specimen *CD-I3* during impact test.

The price of this construction in Washington, D. C., as of July 1937, was \$0.385/ft<sup>2</sup>.

The floor specimens, shown in figure 28, were 12 ft 6 in. long, 4 ft 0 in. wide, and 6 $\frac{5}{32}$  in. deep. Each specimen consisted of six specially edge-




FIGURE 27.—Impact load on partition *CD*.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens *CD-II*, *I2*, and *I3* on the span 7 ft 6 in.

matched planks, *A*, two full-sized joists, *B*, two half-sized joists, *C*, and end members, *D*. The upper face consisted of flooring, *E*. The underside and the ends of the specimen were covered with one coat of lead-and-oil paint applied with a brush.

**Planks.**—The planks, *A*, were spruce, 1 $\frac{3}{4}$  by 7 $\frac{1}{16}$  in. (nominal 2 by 8 in.), 12 ft 6 in. long. One edge of the plank was recessed  $\frac{1}{8}$  by  $\frac{1}{8}$  in., and the opposite edge was matched, as shown in figure 29.

**Joists.**—The full-sized joists, *B*, were spruce, 1 $\frac{1}{8}$  by 5 $\frac{1}{8}$  in. (nominal 2 by 6 in.), 12 ft 6 in. long, grooved  $\frac{1}{8}$  by  $\frac{1}{8}$  in. on two sides,  $\frac{1}{8}$  in. below the edge. The projecting edge of each plank fitted into the groove in the adjacent joist. Sixpenny box nails, spaced 1 to 2 ft, were driven horizontally through the joist at the groove into the projecting edge of the plank on one side. In some specimens the planks on both sides of a joist were fastened to the joist by corrugated

fasteners spaced about 1 ft 6 in. driven from the upper surface of the specimen. The projecting edges of adjacent planks matched and were joined by corrugated fasteners spaced about 1 ft 6 in., crossing the joint and driven from the under side.

The half-sized joists, *C*, were spruce, 2 $\frac{5}{32}$  by 5 $\frac{1}{8}$  in. (nominal 1 by 6 in.), 12 ft 6 in. long, grooved  $\frac{1}{8}$  by  $\frac{1}{8}$  in. on one side,  $\frac{1}{8}$  in. below the upper edge. The projecting edge of the outer plank fitted into the groove in the half-sized joist and was fastened by 6d box nails, 6d common nails, 1 $\frac{1}{2}$ -in. plasterboard nails, or 6d shingle nails. The nails were spaced from 1 to 2 ft and were driven through the half-sized joists into the plank. A strip of perforated hanger iron was fastened along the ends of the planks and extended around the corners of the specimen about 1 in., as shown in figure 28. It was fastened to the half-sized joists and to each plank by two 1 $\frac{1}{2}$ -in. plasterboard nails.

**End members.**—The end members, *D*, were spruce, 1 $\frac{1}{8}$  by 3 $\frac{5}{8}$  in. (nominal 2 by 4 in.), 1 ft 2 $\frac{1}{2}$  in. long, grooved 2 $\frac{1}{2}$  by  $\frac{1}{2}$  in. on one side. The members were inserted between joists at the ends of the specimen and were fastened to the planks by from three to five 6d common nails or 10d common nails toenailed from the groove into the planks. The outer end members were fastened to the half-sized joists by strips of box strapping, about 4 in. long, bent around the bottom edge of the half-sized joist and fastened to the half-sized joist and the end member by either a 3d lath nail or a  $\frac{3}{4}$ -in. roofing nail.

**Flooring.**—The flooring, *E*, was shortleaf pine and consisted of 43 tongued-and-grooved lines of flooring, 2 $\frac{5}{32}$  by 3 $\frac{1}{4}$  in. The strips of flooring were blind-fastened to the planks by either 6d shingle nails or 6d cut flooring nails. There were from four to six nails to each line spaced along its length.

#### (b) *Comments*

Planks and joists are available in soft woods and in thicknesses ranging from 1 $\frac{1}{4}$  to 3 in. In a house of this construction the first-story floor joists rest on the foundation plate and are fastened by nails to the plate and to the wall planks. Second-story joists rest on a wood ribbon nailed to the wall planks. The ends of the joists are notched at the lower edge and

extend in against the recessed wall planks, where they are nailed. If the joists rest on an interior support, the ends of abutting joists are spliced and fastened by nails or bolts.




FIGURE 28.—Floor specimen *CE*.

*A*, planks; *B*, full-sized joists; *C*, half-sized joists; *D*, end members; *E*, flooring.

Finish floors of various kinds may readily be applied to the floor planks. The underside of the floor may be finished with paint, wallboard, or lath and plaster.

This floor construction also is intended for attic floors and roofs if the distance between supports does not exceed 13 ft.

## 2. TRANSVERSE LOAD

Floor specimen *CE-T2* under transverse load is shown in figure 30. The results for floor specimens *CE-T1*, *T2*, and *T3* are shown in table 7 and in figure 31.

In specimen *T1* at a load of 177 lb/ft<sup>2</sup> the half-sized joists split at middepth both between the loading rollers and from one end to midspan. At a load of 211 lb/ft<sup>2</sup> the two inner joists ruptured at knots near midspan, and at the maximum load they ruptured completely. As the deflection increased all the planks ruptured at midspan. In specimen *T2* at a load of

135 lb/ft<sup>2</sup> both half-sized joists split at mid-depth along the entire length of the specimen. At a load of 150 lb/ft<sup>2</sup> one full-sized joist ruptured under both loading rollers, and at 175 lb/ft<sup>2</sup> the other full-sized joist split the entire length of the specimen along the groove in the joist. At the maximum load the full-sized joist split and four planks ruptured between the loading rollers. In specimen *T3* at a load of 175 lb/ft<sup>2</sup> the half-sized joists ruptured at mid-span, at a load of 200 lb/ft<sup>2</sup> both inner joists ruptured at or between the loading rollers, and at the maximum load two planks ruptured at or between the loading rollers. In all specimens the flooring was undamaged, though in specimen *T1* it had separated noticeably from the planks.




FIGURE 29.—Details of floor specimen *CE*.

*A*, planks; *B*, full-sized joist; *C*, half-sized joist; *D*, end member; *E*, flooring.

## 3. CONCENTRATED LOAD

The results for floor specimens *CE-P1*, *P2*, and *P3* under concentrated load are shown in table 7 and in figure 32.




FIGURE 30.—Floor specimen *CE-T2* under transverse load.




FIGURE 31.—Transverse load on floor *CE*.

Load-deflection (open circles) and load-set (solid circles) results for specimen *CE-T1*, *T2*, and *T3* on the span 12 ft 0 in.




FIGURE 32.—Concentrated load on floor *CE*.

Load-indentation results for specimens *CE-P1*, *P2*, and *P3*.

TABLE 7.—*Structural properties, floor CE*[Weight, 7.80 lb/ft<sup>2</sup>]

Load	Load applied	Specimen designation	Maximum height of drop	Maximum load
Transverse	{Upper face; span, 12 ft 0 in.	<i>T<sub>1</sub></i>	ft	lb/ft <sup>2</sup>
		<i>T<sub>2</sub></i>		214
		<i>T<sub>3</sub></i>		237
Concentrated	Upper face	<i>P<sub>1</sub></i> <i>P<sub>2</sub></i> <i>P<sub>3</sub></i>		235
				229
Impact	{Upper face; span, 12 ft 0 in.	<i>I<sub>1</sub></i> <i>I<sub>2</sub></i> <i>I<sub>3</sub></i>		lb.
				<sup>a</sup> 1,000
Impact	Average			<sup>a</sup> 1,000
			<sup>a</sup> 1,000	
Impact	Average			<sup>a</sup> 10.0
				<sup>a</sup> 10.0

<sup>a</sup> Test discontinued. Specimens did not fail.

The concentrated loads were applied between full-sized joists at the corner of an end joint in the flooring either 6 ft or 2 ft from one end of the specimen. The indentations after a load of 1,000 lb had been applied were 0.024, 0.020, and 0.061 in. for specimens *P<sub>1</sub>*, *P<sub>2</sub>*, and *P<sub>3</sub>*, respectively, and no other effect was observed.

#### 4. IMPACT LOAD

The results for floor specimens *CE-I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>* under impact load are shown in table 7 and in figure 33.


The impact loads were applied to the upper face, the sandbag striking the flooring between the full-sized joists. The sets after a drop of 10 ft were 0.034, 0.102, and 0.065 in. for specimens *I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>* respectively, and no other effect was observed.

#### IX. ADDITIONAL COMMENTS BY SPONSOR

Three houses have been built embodying these constructions except that in one the floor planks were tongued and grooved.

The roof construction is similar to the floor construction for both flat or sloping roofs. If the roof is covered with tiles or shingles, they are laid on 1-in. furring strips. For sloping roofs the rafters extend beyond the wall line and are notched to fit the top plate. A ridge

rafter is not required; the ends of the planks are mitered and nailed. Ceilings may be of conventional construction.

FIGURE 33.—*Impact load on floor CE.*

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens *CE-I<sub>1</sub>*, *I<sub>2</sub>*, and *I<sub>3</sub>* on the span 12 ft 0 in.

The description and drawings of the specimens were prepared by E. J. Schell, G. W. Shaw, and T. J. Hanley of the Bureau's Building Practice and Specifications Section, under the supervision of V. B. Phelan.

The structural properties were determined by the Engineering Mechanics Section, under the supervision of H. L. Whittemore and A. H. Stang, with the assistance of the following members of the professional staff: F. Cardile, R. C. Carter, H. Dollar, M. Dubin, A. H. Easton, A. S. Endler, C. D. Johnson, A. J. Sussman, and L. R. Sweetman.

#### X. SELECTED REFERENCES

- American Builder **60**, No. 12, 34-35 (1938).
- American Lumberman **3133**, 35 (1938); **3138**, 24-25 (1938).
- Architectural Forum **69**, 80 (1938); **70**, 246 (1939).
- Architectural Record **86**, 88, 93 (1939).

WASHINGTON, August 5, 1939.



## BUILDING MATERIALS AND STRUCTURES REPORTS

On request, the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C., will place your name on a special mailing list to receive notices of new reports in this series as soon as they are issued. There will be no charge for receiving such notices.

An alternative method is to deposit with the Superintendent of Documents the sum of \$5.00, with the request that the reports be sent to you as soon as issued, and that the cost thereof be charged against your deposit. This will provide for the mailing of the publications without delay. You will be notified when the amount of your deposit has become exhausted.

If 100 copies or more of any report are ordered at one time, a discount of 25 percent is allowed. Send all orders and remittances to the *Superintendent of Documents, U. S. Government Printing Office, Washington, D. C.*

The following publications in this series are now available by purchase from the Superintendent of Documents at the prices indicated:

BMS1	Research on Building Materials and Structures for Use in Low-Cost Housing	10¢
BMS2	Methods of Determining the Structural Properties of Low-Cost House Constructions	10¢
BMS3	Suitability of Fiber Insulating Lath as a Plaster Base	10¢
BMS4	Accelerated Aging of Fiber Building Boards	10¢
BMS5	Structural Properties of Six Masonry Wall Constructions	15¢
BMS6	Survey of Roofing Materials in the Southeastern States	15¢
BMS7	Water Permeability of Masonry Walls	10¢
BMS8	Methods of Investigation of Surface Treatment for Corrosion Protection of Steel	10¢
BMS9	Structural Properties of the Insulated Steel Construction Co.'s "Frameless-Steel" Con- structions for Walls, Partitions, Floors, and Roofs	10¢
BMS10	Structural Properties of One of the "Keystone Beam Steel Floor" Constructions Spon- sored by the H. H. Robertson Co.	10¢
BMS11	Structural Properties of the Curren Fabrihome Corporation's "Fabrihome" Construc- tions for Walls and Partitions	10¢
BMS12	Structural Properties of "Steelox" Constructions for Walls, Partitions, Floors, and Roofs Sponsored by Steel Buildings, Inc.	15¢
BMS13	Properties of Some Fiber Building Boards of Current Manufacture	10¢
BMS14	Indentation and Recovery of Low-Cost Floor Coverings	10¢
BMS15	Structural Properties of "Wheeling Long-Span Steel Floor" Construction Sponsored by the Wheeling Corrugating Co.	10¢
BMS16	Structural Properties of a "Tilecrete" Floor Construction Sponsored by Tilecrete Floors, Inc.	10¢
BMS17	Sound Insulation of Wall and Floor Constructions	10¢
BMS18	Structural Properties of "Pre-Fab" Constructions for Walls, Partitions, and Floors Sponsored by the Harnischfeger Corporation	10¢
BMS19	Preparation and Revision of Building Codes	15¢
BMS20	Structural Properties of "Twachtman" Constructions for Walls and Floors Sponsored by Connecticut Pre-Cast Buildings Corporation	10¢
BMS21	Structural Properties of a Concrete-Block Cavity-Wall Construction Sponsored by the National Concrete Masonry Association	10¢
BMS22	Structural Properties of "Dun-Ti-Stone" Wall Construction Sponsored by the W. E. Dunn Manufacturing Co.	10¢
BMS23	Structural Properties of a Brick Cavity-Wall Construction Sponsored by the Brick Manufacturers Association of New York, Inc.	10¢
BMS24	Structural Properties of a Reinforced-Brick Wall Construction and a Brick-Tile Cavity- Wall Construction Sponsored by the Structural Clay Products Institute	10¢
BMS25	Structural Properties of Conventional Wood-Frame Constructions for Walls, Partitions, Floors, and Roofs	15¢
BMS26	Structural Properties of "Nelson Pre-Cast Concrete Foundation" Wall Construction Sponsored by the Nelson Cement Stone Co., Inc.	10¢
BMS27	Structural Properties of "Bender Steel Home" Wall Construction Sponsored by The Bender Body Co.	10¢
BMS28	Backflow Prevention in Over-Rim Water Supplies	10¢
BMS29	Survey of Roofing Materials in the Northeastern States	10¢
BMS30	Structural Properties of a Wood-Frame Wall Construction Sponsored by the Douglas Fir Plywood Association	10¢
BMS31	Structural Properties of "Insulite" Wall and "Insulite" Partition Constructions Spon- sored by The Insulite Co.	15¢
BMS32	Structural Properties of Two Brick-Concrete-Block Wall Constructions and a Concrete- Block Wall Construction Sponsored by the National Concrete Masonry Association	10¢
BMS33	Plastic Calking Materials	10¢
BMS34	Performance Test of Floor Coverings for Low-Cost Housing: Part 1	10¢
BMS35	Stability of Sheathing Papers as Determined by Accelerated Aging	10¢
BMS36	Structural Properties of Wood-Frame Wall, Partition, Floor, and Roof Constructions with "Red Stripe" Lath Sponsored by the Weston Paper and Manufacturing Co.	10¢
BMS37	Structural Properties of "Palisade Homes" Constructions for Walls, Partitions, and Floors Sponsored by Palisade Homes	10¢

